



वर्गीकृत विज्ञापन

TENDER NOTICE

Sealed quotations are invited from different registered contractors for construction of Boundary wall at DAV Public School, Lalganj, Buxar. Contractors are advised to contact the school office for further details & submit the sealed quotations with all specification and condition to the undersigned office within a fortnight of tendering this notice.

Principal
DAV PS, Lalganj, Buxar

Specification for construction of Boundary Wall at DAV Public School, Buxar. The details are given below:-

Serial	SoR	Particulars	Quantity
BOUNDARY LENGTH = 506' UPTO 10'			5060
1	2.6	Earth work in Excavation including disposal of excavated garbage upto 50 m in all kinds of soil	122.0
2	20.3A.1	Making 25 cm dia. Bore upto 4 metre below ground with hand Auger in ordinary soil and disposal of earth upto 50 m all complete	100.0
3	2.28	Supplying and filling in plinth with Local sand including watering, ramming, consolidating and dressing complete	45.0
4	11.72	Providing designation 100A one brick flat soiling joints filled with local sand complete	60.0
5	4.1.3	Providing PCC (1:2:4) with graded Stone chips of 20 mm nominal size excluding the cost of centring and shuttering all works in Foundation all complete	14.0
6	5.1.2	Providing and Laying in Position RCC M20 with graded stone chips of 20 mm nominal size all works upto plinth level excluding the cost of centering, shuttering and reinforcement	71.0
7	6.1.12 C	Fly ash Brick work with cement mortar (1:4) in Foundation & Plinth	115.0
8	5.9	Centring and shuttering including strutting, propping etc. and removal of form	
	5.9.6	Column	118.0
	5.9.5	Tie beam, Top tie	142.0
9	5.22	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete	
	7A	TMT - 8 mm	1495.0
	7B	TMT - 10 mm	8794.0
	7C	TMT - 12 mm	2990.0
10	10.32.2	Providing and fixing MS Gates @ 25 Kg per Sq m with a coat of approved steel Primer all complete	107.0
11	NS	Angle fixing for safety wire all complete	54.0
12	10.35.5	Fixing 4 rows Barbed wire all complete	154.0
13	10.43	Providing and fixing concertina coil fencing with punched tape metre 289.50 concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5 mm thick) wire of high tensile strength of 165 kg/ sq mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	154.0
14	13.13.4	20 mm (1:6) cement Plaster Over Outer Wall	470.0

15	13.78.1	Providing one coat of cement primer of approved brand and manufacture on wall surface all complete	940.0
16	13.79.1	Providing water proof cement paint of approved brand and manufacture and of required shade to give and even shade three or more coat on new work all complete	940.0
17	13.93.1	Painting with synthetic enamel two or more coats over Wood and Steel Work	12.0

FOLLOWING POINTS NEED ATTENTION

1. Sealed quotations as per above specification must be submitted to the school office DAV Public School, Lalganj, Itarhi Road, Buxar (Bihar) by 15-01-2024. The part credentials/work experience of the contractor must be enclosed.
2. Brand/Quality/quantity must be specified whenever acceptable.
3. Rates quoted should include all applicable taxes & all other expenses; no extra cost will be paid by the school in any case.
4. Lowest rates will be decided after final negotiation with the bidders by the building-sub-committee of the school.