

With reference to letter no. DAV/BXR/2025-26/1179 dated 15-04-2025 approved by Manager, LMC, DAV Public School, Buxar. Specification for Miscellaneous works at DAV Public School, Lalganj, Buxar The details are given below: -

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.
		1. MISCELLANEOUS WORK		
		Area of Repair of glass = 310.50 Sft (28.86 Sqm); Wall tiles=566 Sft; Misc. items;		
1	14.5	Renewing glass panes,with putty and nails wherever necessary including racking out the old putty:		
	14.5.1	Float glass panes of thickness 4 mm.	28.86	Sqm
2	15.56	Dismantling old plaster or skirting racking out joints and clearing the surface for plastering including disposal of rubbish to the dumping ground within 50 metres lead.	52.60	Sqm
3	11.36	Providing and fixing first quality ceramic glazed wall tiles confirming to IS 15622(Thickness to be specified by manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by engineer in charge in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1 cement, 3 coarse sand) and jointed with grey cement slurry @ 3.3 Kg/sqm including pointing in white cement mixed with pigment of matching shade complete.	52.60	Sqm
4	17.7	Providing and fixing wash basin with C.I. brackets 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern including painting of fittings and brackets, cutting and making good the walls wherever required:		
	17.7.7	White Vitreous china Flat back wash basin size 450x 300 mm with single 15 mm C.P. brass pillar tap.	1	Each
5	17.29	Providing and fixing 100 mm sand cast iron grating for gully trap.	20	Each
6	17.71	Providing and fixing PTMT liquid soap container 109 mm wide, 125mm high and 112mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	8	No.
7	18.15	Providing and fixing brass bib cock of approved quality:		
	18.15.1	15 mm nominal bore	40	Each

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.
8	9.1	Providing and fixing alluminium handles anodised (anodic coating not less than grade AC 10 as per IS: 1868)transparent or dyed to required colour or shade with necessary screws etc. Compete.		
	9.100.1	125 mm	20	No.
9	9.97	Providing and fixing alluminium sliding tower bolt anodised(anodic coating not less than grade AC 10 as perIS1868)transparent or dyed to required colour and shade with nuts and screws etc. complete.		
	9.97.1	300x10mm	20	No.
10	9.96	Providing and fixing alluminium sliding door bolt anodised(anodic coating not less than grade AC 10 as perIS1868)transparent or dyed to required colour and shade with nuts and screws etc. complete.		
	9.96.1	300x16mm	10	No.
11	17.23	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260 x50 mm or 340x410x265 mm sizes respectively.	19	Each
12	18.22	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet:		
	18.22.1	100 mm diametre	7	Each
13	PSOR	Providing and fixing external and internal PHE work external and internal electrical works.	LS	
		TOTAL		
		ROUND UP		
		2. PLATFORM FOR DRINKING AT 1ST FLOOR		
		Area of Platform = 12'-2"x4'-9" (with 9" w. step 6" ht.) = 57.76 Sft (5.37 Sqm) ;P		
1	2.28	Supplying and filling in plinth with local sand and under floors including watering, ramming, consolidating and dressing complete.	0.68	Cum
2	6.18.4A + 6.19A	Half brick masonry with bricks of class designation 100A in superstructure above plinth level upto floor V level in cement mortor 1:4 (1 cement; 4 coarse sand).	1.13	Sqm
3	13.11	12 mm thick Cement plaster in course sand of mix:		
	13.11.4	1:6(1 cement: 6 coarse sand)	1.13	Sqm
4	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering-		
	4.1.3	1:2:4 (1 Cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	0.41	Cum
5	11.72	Providing designation 100A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification ad direction of E/I.	5.37	Sqm

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.
6	11.38	Providing and laying Ceramic glazed floor tiles 300x 300 mm (thickness to be specified by the manufacturer) of first quality conforming to IS:15622 of approved make in colours such shades except white, Ivory Grey, Fume Red, Brown laid on 20 mm thick cement mortar 1:4(1 cement: 4 coarse sand)including pointing the joints with white cement and matching pigment etc. complete.	5.37	Sqm
		TOTAL		
		ROUND UP		
		Cost of construction per S.Ft.		
		3. ACP WORK UNDER STAIRS - NEAR BOY'S TOILET & P. ROOM		
		Area of ACP work = 88.01 Sft + 133.15 Sft = 221.16 Sft. (20.55 Sqm)		
1	MR	Providing and fixing aluminium framed doors, sliding windows, ventilators and partitions with Aluminium sections, 4 mm thick plain glass, rubber, handles, door bolts, sliding tower bolts and locks, composite panel etc. complete.	20.55	Sqm

FOLLOWING POINTS NEED ATTENTION

1. Sealed quotations as per above specification must be submitted to the school office DAV Public School, Lalganj, Itarhi Road, Buxar (Bihar) by 30-04-2025. The part credentials/work experience of the contractor must be enclosed.
2. Brand/Quality/quantity must be specified whenever acceptable.
3. Rates quoted should include all applicable taxes & all other expenses; no extra cost will be paid by the school in any case.
4. Lowest rates will be decided after final negotiation with the bidders by the constitution of committee for repair & maintenance, renovation & small construction of the school.
5. Uses of Electricity & Water through the contractor of said works deducted 1% of final approved bills.